



NOTES:

1. WARNING TAPE TO BE INSTALLED 12" BELOW FINAL GRADE IF UNDER NATURAL SOIL OR 18" BELOW FINAL GRADE IF UNDER ASPHALT OR CONCRETE.
2. CONTACT CEC FOR INSPECTION OF CONDUIT INSTALLATION PRIOR TO BACKFILLING TRENCH
3. COMPACTED BACKFILL 95% MODIFIED PROCTOR DENSITY
4. SIZE AND QUANTITY OF CONDUIT AS SPECIFIED ON CONDUIT PLAN.
5. CONDUIT SHALL BE ELECTRICAL GRADE SHEDULE 40 PVC OF SIZE SPECIFIED

ELBOW DESCRIPTION	RADIUS
1" - 90° OR 45°	18"
2.5" - 90° OR 45°	24"
3" - 90° OR 45°	24"
4" - 90° OR 45°	36"
6" - 90° OR 45°	48"

TRENCH DETAIL

REVISED



DRAWN BY:
CJH
DATE:
6-7-06

APPROVED BY:
JWM
SCALE:
NTS